



Ardito Construction Company Inc.

**2216 Wakita Dr. SE
Marietta, GA 30060**

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
11/8/2017	423

Name / Address

Project

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Roadway Repairs

Description	Qty	Unit	Unit Price	Total
Roadway Repairs (Revised) Cobb DOT Specifications				
ORIGINAL ESTIMATE				
4001 Macedonia Road (5 x 6 ft.)				
- Asphalt/ Concrete Saw Cut	20	L.F.	1.00	20.00
- Haul Off (Concrete/ Asphalt)	2.5	C.Y.	20.00	50.00
- Traffic Control (Including Steel Road Plates)	2	EA	250.00	500.00
- Contractor's Hourly Rate	4	Hrs	250.00	1,000.00
NOTE: Excavate Existing Road Cut and Trench Compaction				
- 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt	48	S.F.	10.25	492.00
4001 Macedonia Road Total:				2,062.00
ADDITIONAL REPAIR SPECS				
- 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt	-48	S.F.	10.25	-492.00
- Asphalt/ Concrete Saw Cut	16	L.F.	1.00	16.00
- Haul Off (Concrete Curbing)	1.5	C.Y.	20.00	30.00
- Haul Off (Dirt)	6.67	C.Y.	20.00	133.40
- Contractor's Hourly Rate	5	Hrs.	250.00	1,250.00
NOTE:				
1. "Short Load" Concrete Curbing Fee.				
2. Additional Jackhammer Removal, Excavation and Compaction of Curb Line.				
3. Additional Depth Asphalt Saw Cut.				
4. Landscaping Behind Curb.				
- 12 inches GAB, 7 inches Asphalt Base Placed in 2 Layers, 1" Asphalt Topping Overlay	48	S.F.	16.35	784.80
- 24 inches GDOT Type 2 curb/ gutter	20	L.F.	15.00	300.00
4001 Macedonia Road Total Additions:				2,022.20

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total:



Ardito Construction Company Inc.

**2216 Wakita Dr. SE
Marietta, GA 30060**

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
11/8/2017	423

Name / Address

Project

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Roadway Repairs

Description	Qty	Unit	Unit Price	Total
ORIGINAL ESTIMATE				
3199 Macedonia Road (5 x 6 ft.)				
- Asphalt/ Concrete Saw Cut	20	L.F.	1.00	20.00
- Haul Off (Concrete/ Asphalt)	2.5	C.Y.	20.00	50.00
- Traffic Control (Including Steel Road Plates)	2	EA	250.00	500.00
- Contractor's Hourly Rate	4	Hrs.	250.00	1,000.00
NOTE: Excavate Existing Road Cut and Trench Compaction				
- 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt	48	S.F.	10.25	492.00
3199 Macedonia Road Total:				2,062.00
ADDITIONAL REPAIR SPECS				
- 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt	-48	S.F.	10.25	-492.00
- Asphalt/ Concrete Saw Cut	16	L.F.	1.00	16.00
- Haul Off (Concrete Curbing)	1.5	C.Y.	20.00	30.00
- Haul Off (Dirt)	6.67	C.Y.	20.00	133.40
- Contractor's Hourly Rate	5	Hrs.	250.00	1,250.00
NOTE:				
1. "Short Load" Concrete Curbing Fee.				
2. Additional Jackhammer Removal, Excavation and Compaction of Curb Line.				
3. Additional Depth Asphalt Saw Cut.				
4. Landscaping Behind Curb.				
- 12 inches GAB, 7 inches Asphalt Base Placed in 2 Layers, 1" Asphalt Topping Overlay	48	S.F.	16.35	784.80
- 24 inches GDOT Type 2 curb/ gutter	20	L.F.	15.00	300.00
3199 Macedonia Road Total Additions:				2,022.20

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$8,168.40