



Ardito Construction Company Inc.

2216 Wakita Dr. SE
Marietta, GA 30060

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
8/30/2017	396

Name / Address

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Project

Paddocks Way 1100 Storm Drain Repair

Description	Qty	Unit	Unit Price	Total
Storm Drain Repair				
1100 Paddocks Way				
- Asphalt/ Concrete Saw Cut	40.5	L.F.	1.00	40.50
- Haul Off (Concrete Driveway)	4	C.Y.	45.00	180.00
- 24 in R.C.P. Storm Drain Pipe (4 to 6 ft. in Depth)	40	L.F.	69.95	2,798.00
- 24" C.M.P. Removal and Haul Off	40	L.F.	24.00	960.00
- Connection to Existing Storm Manhole/ Catch Basin	2	EA	850.00	1,700.00
- Concrete Driveway 4 - 6 inches Thick	222.75	S.F.	8.95	1,993.61
- Mulch (Wheat Straw)	288	S.F.	0.15	43.20
- Grading Complete & Permanent Grassing	288	S.F.	2.25	648.00
- Temporary Silt Fence Type A (Sd1-NS)	64	L.F.	3.00	192.00

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$8,555.31