



Ardito Construction Company Inc.

**2216 Wakita Dr. SE
Marietta, GA 30060**

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
11/3/2017	421

Name / Address

Project

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Roadway Repairs

Description	Qty	Unit	Unit Price	Total
Roadway Repairs				
ORIGINAL ESTIMATE				
3021 Old Lost Mountain Road (5 x 11 ft.)				
- Asphalt/ Concrete Saw Cut	25	L.F.	1.00	25.00
- Haul Off (Concrete/ Asphalt)	4	C.Y.	20.00	80.00
- Traffic Control (Including Steel Road Plates)	2	EA	250.00	500.00
- Contractor's Hourly Rate	5	Hrs.	250.00	1,250.00
NOTE: Excavate Existing Road Cut and Trench Compaction				
- 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt	78	S.F.	10.25	799.50
3021 Old Lost Mountain Road Total:				2,654.50
ADDITIONAL REPAIRS				
Total Roadway Repair: 22 x 6 ft.				
- Asphalt/ Concrete Saw Cut	13	L.F.	1.00	13.00
- Haul Off (Concrete/ Asphalt) Including Curb Removal	2.75	C.Y.	20.00	55.00
- Haul Off (Mud/ Unusable Dirt)	13	C.Y.	20.00	260.00
- Traffic Control	1	EA	250.00	250.00
- Contractor's Hourly Rate	10	Hrs.	250.00	2,500.00
NOTE:				
1. Excavate Additional Road Cut Including Additional Depth and Trench Compaction. (Additional Time November 2 & 3, 2017)				
2. Additional Curb Cut Compaction.				
3. Additional Concrete for Flowable Fill of Voids Created By Water Main Failure.				
4. Temorary Road Cut Patch (Cold Patch) in Order to Remove Steel Plates from Roadway and Allow Enough Concrete Curing Time for Hot Patch.				
- 8" GAB, 6" Concrete Trench Cap 1 ft. larger than ditch in all directions, 2" Asphalt	54	S.F.	10.25	553.50
- 24 inches GDOT Type 2 curb/ gutter	22	L.F.	15.00	330.00
Additional Repairs Total:				3,961.50

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$6,616.00