



Ardito Construction Company Inc.

2216 Wakita Dr. SE
Marietta, GA 30060

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
2/22/2018	444

Name / Address

Project

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Woodbridge Ct. 4038 Sewer Main Repair

Description	Qty	Unit	Unit Price	Total
Sewer Main Repair 4038 Woodbridge Court Sewer Main Root Cutting - Jet Sewer Main Up Stream from Manhole in backyard of 4034 Woodbridge Court with Root Cutter Head in Order to Remove Tree Roots. NOTE: 1. Estimate is for up to 4 hours on site. 2. After Hours 6:00pm to 6:00am will be additional cost. 3. Off Site Dump Fees from Vac Unit will be \$285.00 per hour plus \$0.31 per gallon.	1	L.S.	2,590.00	2,590.00
- Sewer Main Point Repair (4 to 6 ft. in Depth) NOTE: Existing Sewer Tap/ Tee Replacement	1	EA	1,825.00	1,825.00
- Sewer Main Point Repair (6 to 8 ft. in Depth) NOTE: 8" Outside Drop Repair/ Tee Replacement	1	EA	2,225.00	2,225.00
- Connection to Existing Manhole	1	EA	550.00	550.00
- Contractor's Hourly Rate	22	Hrs.	250.00	5,500.00
NOTE: 1. Additional Hand Excavation Work in Confined Location. 2. Sewer Main Bypass Pumping from Manhole in Backyard on Woodcrest Trail to 4034 Woodbridge Ct. including additional personnel for pumping operation. 3. Chisel and Removal of Existing Manhole Connection. 4. Additional Sewer Main Pumping from Trench Due to a Hole in the Sewer Main.				
- Contractor's Hourly Rate	9.5	Hrs.	250.00	2,375.00
NOTE: 1. Disassemble Wood Deck, Relocate on Site and Replace as Necessary. 2. Existing Cross-tie Cut, Removal and Haul Off				

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$15,065.00