



Ardito Construction Company Inc.

**1290 Austell Road, SE
Marietta, GA 30008**

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
11/5/2018	539

Name / Address

Project

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Marietta Street Water Main Connection

Description	Qty	Unit	Unit Price	Total
Water Main Connection				
Marietta Street to Pineview Drive				
- 12 x 8" Wet Tap	1	EA	3,750.00	3,750.00
- 3/4" Short Side Water Service for Testing	1	EA	550.00	550.00
- 8" Class 51 D.I.P. (4'-6' depth)	140	L.F.	36.00	5,040.00
- Asphalt/ Concrete Saw Cut	336	L.F.	2.00	672.00
- Haul Off (Concrete/ Asphalt)	30.5	C.Y.	25.00	762.50
- Haul Off (Dirt)	21.75	C.Y.	25.00	543.75
- Change in Direction (8" 45 Degree Bend)	2	EA	400.00	800.00
- Line Valves M&H (8" Line Valve)	1	EA	970.73	970.73
- Reducer (12 x 8")	1	EA	209.00	209.00
- Solid Sleeve (8")	1	EA	177.00	177.00
- Threaded Rod (3/4")	40	L.F.	9.00	360.00
- Chlorinate & Flush Water Main	1	EA	450.00	450.00
- Water Main Tie-in (12 x 8")	1	EA	1,000.00	1,000.00
- Traffic Control	10	EA	250.00	2,500.00
- Contractor's Hourly Rate	6	Hrs.	250.00	1,500.00
NOTE: Locating & Investigating Existing 8" Dead End Water Line where New Connection is to be Made.				
- 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt	292	S.F.	10.25	2,993.00
- 24 inch Vertical Curb	32	L.F.	32.50	1,040.00
- Sidewalk 4 Inches Thick	303	S.F.	7.95	2,408.85
- Sidewalk Brick Paver Band Repair	75	L.F.	10.00	750.00
- Brick Paver Crosswalk & Concrete Brick Band Repair	36	S.F.	120.00	4,320.00
- ADA Ramp Brick Paver Removal and Replacement	2	EA	1,050.00	2,100.00
- Concrete Deadman	1	EA	1,850.00	1,850.00
- Grading Complete	1	L.S.	1,750.00	1,750.00
- Permanent Grassing (SOD)	180	S.F.	2.50	450.00

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$36,946.83