



**Date:** March 29, 2023

**Project:** Stormwater Structure Cleanout on Sailors Parkway

**Recommendation:** Staff recommends awarding contract for cleaning stormwater structures on Richard D. Sailors Parkway HydroExcavators, LLC in the amount of \$14,326.00 using American Rescue Plan Act grant funds.

**Background:** The Mayor and Council chose to direct a portion of the funds from the City's ARPA grant to address stormwater infrastructure needs throughout the City. Staff identified this small project as a significant issue contributing to hazardous conditions on Sailors Parkway during rain storms. Ten stormwater inlets have become severely clogged with silt and debris, some as deep as two feet. Staff solicited quotes from three vendors qualified and experienced to do the work, and HydroExcavators, LLC provided the lowest responsive price quote.

HydroExcavators is a reputable contractor with significant experience in this type of work. Staff recommends awarding the contract for stormwater structure cleaning on Sailors Parkway to HydroExcavators, LLC.

Prepared by: Wayne P. Wright, ARPA Program Manager



# HydroExcavators, LLC.

## Rates

Date : January 24, 2023  
Company Name City Of Powder Springs  
Contact Name John  
Contact Number [REDACTED]  
Project Name **Manhole Cleanout**  
Project Address 3006 Springs Industrial Drive, Powder Springs

OFX Code: Atlanta  
Area: Georgia  
Region: 1

Following is the requested pricing for the subject project.

ITEM NO.	HydroX will jet approx 30' of storm drain. HydroX will dispose material off site. Proposal based on easy access with minimal logistical challenges to max our production. Below is an estimate only. HydroX will invoice for actual time and material on project.	Hyd			
		QTY	UNIT	RATE	TOTAL COST
1	Vac Truck	38	Hourly	\$290.00	\$ 11,020.00
2	Disposals	5	Load	\$275.00	\$ 1,375.00
3	Fuel Surcharge (7% of man hours on site)				\$ 771.00
4	Confined Space	1	Daily	\$500.00	\$ 500.00
5	Additional Non CDL	12	Hourly	\$55.00	\$ 660.00
<b>TOTAL</b>					<b>\$14,326</b>

**Special Notes:** HydroX is not responsible for any erosion control. Large rock, wood, debris, can impact production and project costs.  
Remote work may require additional labor and or equipment at an additional cost. There is a four hour minimum charge.  
Client is responsible for any contamination to soils, spoils, or materials. Unless stated work is billed portal to portal.  
Unstable ground conditions, and or cave ins, could require additional equipment or materials to be provided by the contractor. Remote work could require additional equipment and labor.  
HydroX will be able to work without undue disruption of service or schedule.

PROPOSED BY 

**Hydro-Excavation Specialists**  
**ELECTRICITY - SEWER - WATER - GAS - COMMUNICATIONS**

## **EXHIBIT D**

### **SCOPE OF WORK FOR DRAINAGE STRUCTURE CLEANING ON RICHARD D. SAILORS PARKWAY**

Work is to be performed at ten drainage structures on Richard D. Sailors Parkway between Forest Hill Road and C.H. James Parkway. Structures are precast concrete approximately 15 to 20 feet deep and four feet in diameter. Connecting storm piping is typically 24 inches in diameter.

Remove dirt, trash, stones, concrete, and any other debris from the structures and the connecting pipes.

Clean the structures with high-pressure water jet.

Dispose of any material off site.

Provide any needed traffic control.

Contractor is responsible for protecting the safety of its employees through compliance with OSHA regulations, including confined space entry training and procedures.