



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
5/8/2018	474

Name / Address

Project

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Repair Work

Description	Qty	Unit	Unit Price	Total
Repair Work				
3241 Hopkins Road				
- Asphalt/ Concrete Saw Cut	8	L.F.	2.00	16.00
- Haul Off (Dirt)	0.5	C.Y.	25.00	12.50
- Traffic Control	1	EA	250.00	250.00
- Contractor's Hourly Rate	3.5	Hrs.	250.00	875.00
NOTE:				
1. Excavation and Compaction of Existing Sidewalk Cut.				
2. "Short Load" Concrete Fee.				
3. Grading Complete				
- Sidewalk 4 inches Thick	20	S.F.	7.95	159.00
3241 Hopkins Road Total:				1,312.50
3827 New Macland Road				
- Asphalt/ Concrete Saw Cut	10	L.F.	2.00	20.00
- Haul Off (Dirt)	1	C.Y.	25.00	25.00
- Traffic Control	1	EA	250.00	250.00
- Contractor's Hourly Rate	4	EA	250.00	1,000.00
NOTE:				
1. Excavation and Compaction of Existing Sidewalk Cut.				
2. "Short Load" Concrete Fee.				
3. Grading Complete				
- Sidewalk 4 inches Thick	55	S.F.	7.95	437.25
3827 New Macland Road Total:				1,732.25
Cobb DOT Specifications				
3318 Macedonia Road (4 x 5 ft.)				
- Asphalt/ Concrete Saw Cut	18	L.F.	2.00	36.00
- Haul Off (Concrete/ Asphalt)	1.5	C.Y.	25.00	37.50

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total:



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
5/8/2018	474

Name / Address

Project

City of Powder Springs 3006 Springs Industrial Dr. Powder Springs, Ga. 30127
--

Repair Work

Description	Qty	Unit	Unit Price	Total
- Traffic Control	1	EA	250.00	250.00
- Contractor's Hourly Rate	8	Hrs.	250.00	2,000.00
NOTE: 1. Excavation and Compaction of Existing Road Cut. 2. Additional Jackhammer Removal. 3. Additional Depth Asphalt Saw Cut. 4. No Curbing Shall Be Removed Due to Conflicts with the Catch Basin Throat and Top.				
- 12 inches GAB, 7 inches Asphalt Base Placed in 2 Layers, 1" Asphalt Topping Overlay	20	S.F.	36.35	727.00
3318 Macedonia Road Total:				3,050.50

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$6,095.25