

Below are results for quotations received for Storm Water Repairs work at 4178 and 4179 Woodcrest Drive for your review.

Knight and Associate Incorporated - \$ 44,350.00

Ardito Construction Company incorporated - \$ 70,844.00

SC&D Incorporated – Decline to offer a bid

SCA Construction – No response to the bid

Knight & Associates, Inc.

Utilities & General Contractors & Engineering Services

May 14, 2018

Michael Asiedu
City of Powder Springs

Re- Solicitation for Storm Drain Pipe at 4178 and 4179 Woodcrest Drive.

- Secure utility locate and pothole area..... \$1,250
- Remove 180 Feet long Storm Drain Pipe, 30 inches diameter Corrugated Metal Pipe and replace with 30 inches Diameter R.C.P Storm Water Pipe \$18,500
- Allow for road crossing for the R.C.P and replace in kind all road materials for the road repairs.....\$6,900
- Allow for removal of four trees.....\$7,500
- Allow for removal and replacement part of chain-link fence at 4179 Woodcrest Drive.... \$1,900
- Allow provision for traffic control, road closer and BMP'S.....\$3,900
- Allow desilting all ditch line to ensure continuous flow of storm water.....\$2,900
- Provide adequate measures to seal off all joints between the existing catch basin and the new drain pipes to prevent leaks in the future.....\$1,900
- Ensure inlet and outlet pipe system has a positive drainage\$1,500
- Lump sum Total.....\$44,350.00

Regards,

Kamal S. Abiodun, P.G.
Principal



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

ARDITO
CONSTRUCTION COMPANY INC.
MEMBER OF THE ARDITO GROUP

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
5/11/2018	475

Name / Address

Project

City of Powder Springs 3006 Springs Industrial Dr. Powder Springs, Ga. 30127
--

Woodcrest Drive 4178/ 4179 Storm Drain
--

Description	Qty	Unit	Unit Price	Total
Storm Drain Replacement				
4178/ 4179 Woodcrest Drive				
- Asphalt/ Concrete Saw Cut	56	L.F.	2.00	112.00
- Haul Off (Concrete/ Asphalt)	32.5	C.Y.	25.00	812.50
- Haul Off (Dirt)	20	C.Y.	25.00	500.00
- Traffic Control	1	L.S.	2,500.00	2,500.00
- Clearing and Grubbing (Tree Removal)	1	L.S.	6,800.00	6,800.00
- Chain Link Fence Removal & Replacement	20	L.F.	20.00	400.00
- 30 inch C.M.P. Storm Drain Pipe Removal and Haul Off	180	L.F.	30.00	5,400.00
- Connection to Existing Storm Sewer Manhole	4	EA	550.00	2,200.00
- 30 inch R.C.P. Storm Drain Pipe (6 to 8 ft. Depth)	180	L.F.	156.35	28,143.00
- 30 inch Precast Concrete Headwall	2	EA	1,190.00	2,380.00
- Catch Basin Throat/Top Removal and Replacement	2	EA	4,425.00	8,850.00
- Type III Rip Rap (Inlet and Outlet Protection)	10	Ton	105.00	1,050.00
- 24 inches GDOT Type 2 curb/ gutter	50	L.F.	32.50	1,625.00
- 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt	480	S.F.	10.25	4,920.00
- Grading Complete	1	L.S.	2,500.00	2,500.00
- Permanent Grassing	3,120	S.F.	0.85	2,652.00

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$70,844.50

Michael Asiedu

From: Tony Adibe <sdandcinc@yahoo.com>
Sent: Monday, May 07, 2018 5:41 PM
To: Michael Asiedu
Subject: Re: 4178 and 4179 Woodcrest Drive

Michael,

How are you? Sorry we will not be able to send in a bid to you on this one. We are pretty much covered up for now. Thanks.

Tony

On May 7, 2018, at 10:30 AM, Michael Asiedu <masiedu@CityOfPowderSprings.org> wrote:

The city of Powder Springs is soliciting your quote from replacement of Storm Drain Pipe at 4178 and 4179 Woodcrest Drive.

The scope of work includes the following and must comply with local, state and federal regulations.

- Remove 180 Feet long Storm Drain Pipe, 30 inches diameter Corrugated Metal Pipe and replace with 30 inches Diameter R.C.P Storm Water Pipe
- Allow for road crossing for the R.C.P and replace in kind all road materials for the road repairs.
- Allow for removal of four trees.
- Allow for removal and replacement part of chain-link fence at 4179 Woodcrest Drive.
- Allow provision for traffic control, road closer and BMP'S.
- Allow desilting all ditch line to ensure continuous flow of storm water
- Provide adequate measures to seal off all joints between the existing catch basin and the new drain pipes to prevent leaks in the future

Please, you are required to visit the proposed sites to acquaint yourself with the scope of work before submitting your quote by Monday May 14, 2018 at 12.00pm.

For further questions please contact me via email.

Thank you,
Michael Asiedu

Michael Asiedu

From: Tommy Smith <mailscaconstruction@gmail.com>
Sent: Tuesday, May 08, 2018 6:21 PM
To: Michael Asiedu
Cc: Michael Anderson
Subject: Re: 4178 and 4179 Woodcrest Drive

Hi Michael,

This is Luke in the SCA office. Thanks for the email. We will be in touch ASAP!

Thanks,

Luke

Luke Lovell
Office Manager
SCA Construction
770-547-2439

On Mon, May 7, 2018 at 10:29 AM, Michael Asiedu <masiedu@cityofpowdersprings.org> wrote:

The city of Powder Springs is soliciting your quote from replacement of Storm Drain Pipe at 4178 and 4179 Woodcrest Drive.

The scope of work includes the following and must comply with local, state and federal regulations.

- Remove 180 Feet long Storm Drain Pipe, 30 inches diameter Corrugated Metal Pipe and replace with 30 inches Diameter R.C.P Storm Water Pipe
- Allow for road crossing for the R.C.P and replace in kind all road materials for the road repairs.
- Allow for removal of four trees.
- Allow for removal and replacement part of chain-link fence at 4179 Woodcrest Drive.
- Allow provision for traffic control, road closer and BMP'S.
- Allow desilting all ditch line to ensure continuous flow of storm water
- Provide adequate measures to seal off all joints between the existing catch basin and the new drain pipes to prevent leaks in the future