



Croy Engineering, LLC
200 North Cobb Parkway
Building 400, Suite 413
Marietta, Georgia 30062

Phone: 770.971.5407
Fax: 770.971.0620

www.croyengineering.com

Date: September 22, 2021

Project: **Powder Springs Oakview Drive Drain Project**

Bids were received for The Powder Springs Oakview Drive Drain Project contract on September 22, 2021.

The bids have been reviewed and the corrected bid amounts are listed below:

<u>BIDDER</u>	<u>TOTAL AMOUNT</u>
S.H. Creel Contracting	\$7,155.00
Brothers Construction Group, LLC	\$8,600.00
Ardito Construction Company Inc.	\$10,689.00

It is the recommendation of Croy Engineering, LLC the Program Manager for the City of Powder Springs, to award the contract to **S.H. Creel Contracting**

Sincerely,

Chad R. Kastner
Program Manager

S.H. Creel Contracting

756 WHITE BLOSSOM CT
POWDER SPRINGS, GA 30127-6416
US
screel@shcreel.com
www.shcreel.com



Estimate

ADDRESS
City of Powder Springs
4484 Marietta Street
Powder Springs, GA 30127

ESTIMATE 1025
DATE 09/19/2021
EXPIRATION DATE 10/19/2021

DATE	ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	French Drain	Install French Drain at Oakview Drive at Thurman Springs Park - Per Detail Provided	1	7,155.00	7,155.00

Exclusions:
1. Striping
2. Permits
3. Advanced Warning TC Signs

TOTAL

\$7,155.00

Accepted By

Accepted Date

**Brothers Construction Group, LLC
4629 Rolling Brook Court
Union City, Georgia 30291**

Quote

September 13,2021

**For: Trench Drain
Oak View Drive**

**City of Powder Springs
Powder Springs, GA**

Saw cut for and install 40 LF of French Drain.

- 1) Cut an opening 40 foot long, by minimum 12 inches wide and 36 inches deep.**
- 2) Install 4 inches perforated pipe connected into catch basin cover with 27 inches 57 stone then cover with 16 inches compacted G.A.B., then Cap with 3 inches of Asphalt topping.
Use non-woven fabric.**
- 3) Haul away all the debris.**

\$8,600.00

**With a question feel free to call me: 678-699-5717
Teddyboston1466@gmail.com**



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
9/21/2021	861

Name / Address

Project

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Oakview Drive Trench Drain

Description	Qty	Unit	Unit Price	Total
Trench Drain Installation				
Oakview Drive at Thurman Springs Park				
- Asphalt/ Concrete Saw Cut	160	L.F.	3.00	480.00
- Haul Off (Concrete/ Asphalt)	11	C.Y.	85.00	935.00
- Haul Off (Dirt/ Mud)	8	C.Y.	35.00	280.00
- Traffic Control	2	EA	350.00	700.00
- 4" Trench Drain Per Trench Drain Layout Plan and Detail Provided	40	L.F.	84.50	3,380.00
- Connection to Existing Storm Sewer Drop Inlet	1	L.S.	1,050.00	1,050.00
- 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt	160	S.F.	12.90	2,064.00
- Handicap Parking Paint and 4" Thermoplastic White Hatch Repair	1	L.S.	1,800.00	1,800.00

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$10,689.00