

PUBLIC WORKS DEPARTMENT

Results of Request For Quotes (RFQ) for Infrastructure repairs at New Macland Rd, Steading Rd., Splitwood Way, Sharon Woods Dr., Glen Dr., Elliot Rd., Lockerbie Ln., Dogwood Dr., Groveland Park, Vineridge Dr., Ponderosa Ln., Lewis Rd. Ext., and Nectar Dr.

NAME OF COMPANY	Quote Amount		REMARKS
1 S.H Creal Contracting	\$110,220.00		
2 Ardito Construction	\$89,631.50		
3 DAF Concrete	\$68,300.00		Recommended for the award at \$68,300.00



Proposal

S.H. Creel Contracting
 756 White Blossom Court
 Powder Springs, GA 30127

To: City Of Powder Springs	Contact: Dwayne Eberhart
Address: 1114 Richard Sailors Parkway Powder Springs, GA 30127 UNITED STATES	Phone: (770) 943-1666
Project Name: Infrastructure Repairs - Sidewalks And Curb	Fax:
Project Location: Multiple Locations, Powder Springs, GA	Bid Number:
	Bid Date: 4/2/2026

Item Description	Estimated Quantity	Unit	Unit Price	Total Price
TRAFFIC CONTROL	1.00	LS	\$10,090.00	\$10,090.00
MILL & OVERLAY - 1.5" 9.5MM WITH LIME	218.00	SY	\$128.00	\$27,904.00
MILL - 3.5"	70.00	SY	\$117.00	\$8,190.00
OVERLAY - 2" 19MM, 1.5" 9.5MM WITH LIME	70.00	SY	\$157.00	\$10,990.00
REMOVE & REINSTALL SIDEWALK, CURB & GUTTER & CATCH BASIN TOPS	1.00	LS	\$53,046.00	\$53,046.00

Base Bid Price Subtotal: \$110,220.00

Total Bid Price: \$110,220.00

Notes:

- No Permit or other fees Included.
- SH Creel Contracting will remove all of their spoils, demo and trash.

<p>ACCEPTED: The above prices, specifications and conditions are satisfactory and hereby accepted.</p> <p>Buyer: _____</p> <p>Signature: _____</p> <p>Date of Acceptance: _____</p>	<p>CONFIRMED: S.H. Creel Contracting</p> <p>Authorized Signature: _____</p> <p>Estimator: Michael Ferriss _____</p>
--	---



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

Estimate

Date	Estimate #
4/2/2026	1377

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: [REDACTED]

E-mail: [REDACTED]

Name / Address

City of Powder Springs 3006 Springs Industrial Dr. Powder Springs, Ga. 30127
--

Project

Infrastructure Repair 04/02/26

Description	Qty	Unit	Unit Price	Total
<p>Infrastructure Repair at Multiple Locations</p> <p>Contractor shall provide all labor, materials, equipment, and incidentals necessary to perform infrastructure repairs, including but not limited to:</p> <ul style="list-style-type: none"> • Removal and replacement of sidewalk sections • Removal and replacement of curb and gutter • Removal and replacement/adjustment of catch basin tops, and lids • Asphalt removal and replacement associated with repairs • Pouring of monolithic concrete sections where applicable • Site restoration, including grading and cleanup <p>Project Locations</p> <ul style="list-style-type: none"> • 3529 New Macland Rd. – Sidewalk (10' x 5') • 4211 Steading Rd. – Catch basin top, curb & gutter (12x5 Double Wing and 5ft curb) • 3270 New Macland – Catch basin top • 3376 Splitwood Way – Curb (4 LF x 16') • 4050 Sharon Woods Dr. – Catch basin top • 4170 Glen Dr – Catch basin top • Elliott Rd. – Sidewalk (98' x 5') • 3739 Lockerbie Ln. – Sidewalk (12' x 5') • Dogwood Dr. – Sidewalk around catch basin (2' x 3') • 4082 Groveland Park Dr. – Sidewalk around catch basin (5' x 2') • 4103 Groveland Park Dr. – Sidewalk around catch basin (5' x 2') • 4143 Groveland Park Dr. – Curb (13 LF) • 4193 Groveland Park Dr. – Sidewalk around catch basin (15' x 5') • 2965 Vine Ridge Dr. – Sidewalk around catch basin (5' x 17') • 4129 Vine Ridge Dr. – <ul style="list-style-type: none"> o Sidewalk around catch basin (5' x 15') o Curb & gutter (3' x 15') 				

Please Call Me If You Have Any Questions Or Concerns: [REDACTED]

Estimate Total:



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

Estimate

Date	Estimate #
4/2/2026	1377

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: [REDACTED]

E-mail: [REDACTED]

Name / Address

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Project

Infrastructure Repair 04/02/26

Description	Qty	Unit	Unit Price	Total
• 3360 Dogwood Dr. – o Sidewalk (5' x 25') o Curb (5 LF)				
• Ponderosa Ln. – Asphalt (7' x 22')				
• Lewis Rd. Extension – Asphalt (25' x 25')				
• Golden Jubilee / Nectar Dr. – Asphalt (70' x 25' x 20')				
- Grading Complete	1	L.S.	16,500.00	16,500.00
- Asphalt/ Concrete Saw Cut	380	L.F.	5.00	1,900.00
- Haul Off (Concrete)	180	C.Y.	65.00	11,700.00
- Sidewalk 4 inches Thick	1,000	S.F.	10.00	10,000.00
- Catch Basin Top Replacement	4	EA	2,200.00	8,800.00
- 24 inch Curb & Gutter	38	L.F.	52.50	1,995.00
- Hot Mix Asphalt Construction	2,354	S.F.	12.25	28,836.50
- Traffic Control	18	EA	550.00	9,900.00

Please Call Me If You Have Any Questions Or Concerns [REDACTED]

Estimate Total: \$89,631.50



QUOTE

212 Hicks Drive
 Marietta, GA, 30060
 P: [REDACTED]
 Cell: [REDACTED]

DATE: April 2, 2026
 QUOTE
 Customer ID: Dwayne Eberhart

TO **CITY OF POWDER SPRINGS**

SALESPERSON	WORK ORDER	PO	DATE OF COMPLETION
Antonio Sanchez			

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	LINE TOTAL
3529 New Macland Rd (10' x 5')					
	Sidewalk Repair	1	LS	\$ 700.00	\$ 700.00
4211 Steading Rd. (12x5 Double Wing and 5ft curb)					
	Catch Basin Lid	1	EA	\$ 2,500.00	\$ 2,500.00
3270 New Macland - Catch basin top					
	Catch Basin Lid	1	EA	\$ 2,500.00	\$ 2,500.00
3376 Splitwood Way - Curb (4 LF x 16')					
	Curb Repair	1	LS	\$ 700.00	\$ 700.00
4050 Sharon Woods Dr. - Catch basin top					
	Catch Basin Lid	1	EA	\$ 2,500.00	\$ 2,500.00
4170 Glen Dr - Catch basin top					
	Catch Basin Lid	1	EA	\$ 2,500.00	\$ 2,500.00
Elliott Rd. - Sidewalk (98' x 5')					
	Sidewalk Repair	1	LS	\$ 5,500.00	\$ 5,500.00
3739 Lockerbie Ln. - Sidewalk (12' x 5')					
	Sidewalk Repair	1	LS	\$ 600.00	\$ 600.00
Dogwood Dr.					
	Sidewalk Repair	1	LS	\$ 600.00	\$ 600.00
4082 Groveland Park Dr. (5' x 2')					
	Sidewalk Repair	1	LS	\$ 600.00	\$ 600.00
4103 Groveland Park Dr. (5' x 2')					
	Sidewalk Repair	1	LS	\$ 600.00	\$ 600.00
4143 Groveland Park Dr. (5' x 2')					
	Curb Repair	1	LS	\$ 600.00	\$ 600.00
4193 Groveland Park Dr. (15' x 5')					
	Sidewalk Repair	1	LS	\$ 1,000.00	\$ 1,000.00
2965 Vine Ridge Dr. - (5' x 17')					
	Sidewalk Repair	1	LS	\$ 1,100.00	\$ 1,100.00
4129 Vine Ridge Dr. -					

	Sidewalk Repair	1	LS	\$ 1,000.00	\$ 1,000.00
	Curb Repair	1	LS	\$ 800.00	\$ 800.00
3360 Dogwood Dr. -					
	Sidewalk Repair	1	LS	\$ 1,500.00	\$ 1,500.00
	Curb Repair	1	LS	\$ 500.00	\$ 500.00
Ponderosa Ln. - Asphalt (7' x 22')					
	Asphalt Repair	1	LS	\$ 2,500.00	\$ 2,500.00
Lewis Rd. Extension - Asphalt (25' x 25')					
	Asphalt Repair	1	LS	\$ 7,000.00	\$ 7,000.00
Golden Jubilee / Nectar Dr.					
	Asphalt Repair	1	LS	\$ 18,000.00	\$ 18,000.00
	Traffic Control	\$ 1.00	LS	\$ 10,000.00	\$ 10,000.00
	Mobilization	\$ 1.00	LS	\$ 5,000.00	\$ 5,000.00
					SUBTOTAL
					\$68,300.00
					SALES TAX
					TOTAL
					\$68,300.00

DAF Concrete, Inc.
THANK YOU FOR YOUR BUSINESS!