



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
6/19/2018	490

Name / Address

Project

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Ponderosa Lane 3655 Repair Work

Description	Qty	Unit	Unit Price	Total
Water Leak/ Roadway Repair Work				
3655 Ponderosa Lane (13 x 7 ft.)				
- Asphalt/ Concrete Saw Cut	33	L.F.	2.00	66.00
- Haul Off (Concrete/ Asphalt)	1.5	C.Y.	25.00	37.50
- Haul Off (Dirt/ Crusher Run)	5.5	C.Y.	25.00	137.50
- Traffic Control	3	EA	250.00	750.00
- Contractor's Hourly Rate	11	Hrs.	250.00	2,750.00
NOTE:				
1. Excavation and Compaction of Existing Road Cut				
2. "Short Load" Concrete Fee.				
3. Grading Complete				
- 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt	91	S.F.	10.25	932.75
- Permanent Grassing with Sod	200	S.F.	2.50	500.00
- Permanent Grassing with Seed and Erosion Control Matting	200	S.F.	2.00	400.00

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$5,573.75