



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
8/20/2018	510

Name / Address

Project

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Water Main Break/ Roadway Repairs

Description	Qty	Unit	Unit Price	Total
Roadway Repair Cobb DOT Specifications Additional Repairs Old Lost Mountain Road at Shipp Road (To Repair 25 x 24 ft. Total Roadway Section)				
- Haul Off (Concrete/ Asphalt)	3.5	C.Y.	25.00	87.50
- Haul Off (Dirt/ Gravel)	12.5	C.Y.	25.00	312.50
- Traffic Control (Including Road Closure Detour: Steading Road to New Macland Road to Macedonia Road & Vice Versa)	3	EA	250.00	750.00
- Contractor's Hourly Rate (Two Days)	19	Hrs	250.00	4,750.00
NOTE: 1. Excavate Existing Road Cut, Including Additional Damages Caused By Water Main Break. 2. Trench Compaction 3. Temporary Road Repair with Cold Patch 4. Excavation and Compaction of Curb Line. 5. Additional Depth Asphalt Saw Cut. 6. Landscaping Behind Curb.				
- 12 inches GAB, 7 inches Asphalt Base Placed in 2 Layers, 1" Asphalt Topping Overlay	390	S.F.	16.35	6,376.50
- 24 inches GDOT Type 2 curb/ gutter	25	L.F.	32.50	812.50
- Pavement Striping Repair/ Replacement (Additional 65 L.F. of Thermoplastic)	1	L.S.	1,850.00	1,850.00

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$14,939.00