

Please, below are results of quotation received for Famborough Drive
near Spring Industrial Drive intersection repairs

Ardito Construction Company - \$ 29,867.00

International Business Solutions – No Response

DAF Concrete Work – No Response

Thank you

Michael Asiedu



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

ARDITO
CONSTRUCTION COMPANY INC.
TRADE SHOW PARTICIPANTS

Phone/ Fax: 770-435-3776
E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
4/20/2018	462

Name / Address

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Project

Fambrough/ Spring Ind. Dr. Road Repair

Description	Qty	Unit	Unit Price	Total
Roadway Repair				
Fambrough Drive and Spring Industrial Drive Intersection				
- Asphalt/ Concrete Saw Cut	74	L.F.	2.00	148.00
- Haul Off (Concrete/ Asphalt)	18	C.Y.	25.00	450.00
- Haul Off (Dirt/ Debris)	178	C.Y.	32.50	5,785.00
- Haul In (Suitable Backfill)	178	C.Y.	25.00	4,450.00
- Traffic Control	4	EA	250.00	1,000.00
- Contractor's Hourly Rate (Excavating/ Investigating Road Base and Compaction)	31.5	Hrs	250.00	7,875.00
- 24 inches GDOT Type 2 curb/ gutter	40	L.F.	32.50	1,300.00
- 10 inches GAB, 3" of Asphalt Binder, 1.5" of Type E Mix	588	S.F.	14.25	8,379.00
- Grading Complete & Permanent Grassing	480	S.F.	1.00	480.00

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$29,867.00