



# Ardito Construction Company Inc.

**1290 Austell Road, SE  
Marietta, GA 30008**

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

## Estimate

| Date      | Estimate # |
|-----------|------------|
| 5/29/2018 | 482        |

|                |
|----------------|
| Name / Address |
|----------------|

|                                                                                    |
|------------------------------------------------------------------------------------|
| City of Powder Springs<br>3006 Springs Industrial Dr.<br>Powder Springs, Ga. 30127 |
|------------------------------------------------------------------------------------|

|         |
|---------|
| Project |
|---------|

|                                         |
|-----------------------------------------|
| Frank Aiken Road 4510/ 4533 Repair Work |
|-----------------------------------------|

| Description                                                                                                                     | Qty  | Unit | Unit Price | Total    |
|---------------------------------------------------------------------------------------------------------------------------------|------|------|------------|----------|
| Water Line/ Roadway Repair Work                                                                                                 |      |      |            |          |
| 4510 Frank Aiken Road (7 x 8 ft.)                                                                                               |      |      |            |          |
| - Asphalt/ Concrete Saw Cut                                                                                                     | 23   | L.F. | 2.00       | 46.00    |
| - Haul Off (Concrete/ Asphalt)                                                                                                  | 1    | C.Y. | 25.00      | 25.00    |
| - Haul Off (Dirt/ Crusher Run)                                                                                                  | 1.75 | C.Y. | 25.00      | 43.75    |
| - Traffic Control                                                                                                               | 1    | EA   | 250.00     | 250.00   |
| - Contractor's Hourly Rate                                                                                                      | 3    | Hrs. | 250.00     | 750.00   |
| NOTE:                                                                                                                           |      |      |            |          |
| 1. Excavation and Compaction of Existing Road Cut.                                                                              |      |      |            |          |
| 2. "Short Load" Concrete Fee.                                                                                                   |      |      |            |          |
| - 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt | 56   | S.F. | 10.25      | 574.00   |
| 4510 Frank Aiken Road Total:                                                                                                    |      |      |            | 1,688.75 |
| 4533 Frank Aiken Road (20 x 8ft.)                                                                                               |      |      |            |          |
| - Asphalt/ Concrete Saw Cut                                                                                                     | 36   | L.F. | 2.00       | 72.00    |
| - Haul Off (Concrete/ Asphalt)                                                                                                  | 3    | C.Y. | 25.00      | 75.00    |
| - Haul Off (Dirt/ Crusher Run)                                                                                                  | 5    | C.Y. | 25.00      | 125.00   |
| - Traffic Control                                                                                                               | 1    | EA   | 250.00     | 250.00   |
| - Contractor's Hourly Rate                                                                                                      | 5    | EA   | 250.00     | 1,250.00 |
| NOTE:                                                                                                                           |      |      |            |          |
| 1. Excavation and Compaction of Existing Road Cut.                                                                              |      |      |            |          |
| 2. "Short Load" Concrete Fee.                                                                                                   |      |      |            |          |
| - 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt | 160  | S.F. | 10.25      | 1,640.00 |
| 4533 Frank Aiken Road Total:                                                                                                    |      |      |            | 3,412.00 |

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

**Estimate Total:**

\$5,100.75