



Ardito Construction Company Inc.

**2216 Wakita Dr. SE
Marietta, GA 30060**

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
5/17/2017	365

Name / Address

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Project

Modification of Ramp at City Hall

Description	Qty	Unit	Unit Price	Total
Modification of Ramp at City Hall				
4484 Marietta Street				
- Asphalt/ Concrete Saw Cut	78	L.F.	1.00	78.00
- Haul Off (Concrete/ Brick)	15	C.Y.	20.00	300.00
- Contractor's Hourly Rate	8	Hrs.	250.00	2,000.00
NOTE: Jackhammer & Removal of Existing Ramp, Curbing and Brick Paver Sidewalk Sections.				
- 8" Thermoplastic Crosshatch Striping w/ "No Parking" words on the Ground. (The Words Will Be Paint and 4" or 5" Thermoplastic Crosshatch Is Recommended)	1	L.S.	2,850.00	2,850.00
- Parking Lot Concrete Paving Repair 8" inches Thick	252	S.F.	10.95	2,759.40
- GDOT Type B, ADA Ramp (Including Brick Work)	1	L.S.	14,540.00	14,540.00
NOTE: "Use the same brick pavers to construct Georgia Department of Transportation Standard type B Ramp" 1. The Existing Brick Pavers Cannot Be Reused do to the Mortar Joints. Attempting to Separate & Remove Mortar from the Brick will Be Very Time Consuming & Will Break the Brick. (New Red Brick Paver Material Will Be Matched As Close As Possible To Existing) 2. A GDOT Type A and Type B May Have to Be Combined in Order to Retrofit the Existing Conditions. - 24" wide truncated dome pad to match with existing brick pavers color and the width of the ramp landing area.				

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$22,527.40