



Ardito Construction Company Inc.

1290 Austell Road, SE
Marietta, GA 30008

ARDITO
CONSTRUCTION COMPANY INC.
GEORGIA UTILITY CONTRACTOR

Phone/ Fax: 770-435-3776

E-mail: chuck.ardito@arditoconstruction.com

Estimate

Date	Estimate #
5/8/2018	470

Name / Address

Project

City of Powder Springs
3006 Springs Industrial Dr.
Powder Springs, Ga. 30127

Dogwood Drive 3670 Sewer Repair

Description	Qty	Unit	Unit Price	Total
Repairs Around Sewer Manhole				
3670 Dogwood Drive				
ORIGINAL ESTIMATE:				
- Asphalt/ Concrete Saw Cut	83	L.F.	2.00	166.00
- Haul Off (Concrete/ Asphalt)	18	C.Y.	25.00	450.00
- Haul Off (Dirt & Unsuitable Backfill)	13.5	C.Y.	25.00	337.50
- Haul Off (Haul In Suitable Backfill & # 57 Stone)	13.5	C.Y.	25.00	337.50
- Traffic Control (Including Steel Road Plates)	4	EA	250.00	1,000.00
- Adjust to Grade - Manhole Ring & Cover - Pavement/ Concrete Area	1	EA	425.00	425.00
- Contractor's Hourly Rate	9	Hrs.	250.00	2,250.00
NOTE:				
1. Excavating/ Investigating Existing Road Settlement, Backfill and Compaction				
- 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt	262	S.F.	10.25	2,685.50
ORIGINAL ESTIMATE TOTAL:				7,651.50
ADDITIONAL WORK: (20 x 4 ft. Road Cut)				
- Asphalt/ Concrete Saw Cut	44	L.F.	2.00	88.00
- Haul Off (Concrete/ Asphalt)	3	C.Y.	25.00	75.00
- Haul Off (Dirt & Unsuitable Backfill)	12	C.Y.	25.00	300.00
- Haul Off (Haul In Suitable Backfill & # 57 Stone)	12	C.Y.	25.00	300.00
- Traffic Control	1	EA	250.00	250.00
- Contractor's Hourly Rate	4.5	Hrs.	250.00	1,125.00
NOTE: Excavating & Compaction of Existing Sewer Main Ditch Line (6 to 8 ft. Depth)				
- 8 inches GAB, 6 inches Concrete, Trench Cap 1 foot larger than ditch in all directions Tack Coat 2 inches Type E or F Asphalt	80	S.F.	10.25	820.00
ADDITIONAL WORK TOTAL:				2,958.00

Please Call Me If You Have Any Questions Or Concerns:(678) 618-0240

Estimate Total: \$10,609.50