



APEC QUOTATION WORK FORM



Quotation To

CITY OF POWDER SPRINGS

Date

8-06-20

3006 SPRING IND. DR.

Terms

TBD

POWDER SPRINGS, GA. 30127

Install #

770-943-8013

Cell

Quote #

770-943-8013

Contact

LATISHA HAMMONDS

Email

lhammonds@cityofpowdersprings.org

QTY	Item Number	Description	MSRP	Cost	Sell	Total
		FUEL ISLAND UPGRADE				
2	3672010/266HJKUY	WAYNE "SELECT" ELECTRONIC FLEET FUEL DISPENSER, SINGLE HOSE				
		SINGLE PRODUCT ISLAND ORIENTED WITH: PULSE OUTPUT,			4495. ⁰⁰	8990. ⁰⁰
		INTERNAL FILTER (PAINTED SILVER W/ BLUE DOORS)				
2	DS-1928	ONE-PIECE POLYETHYLENE DISPENSER PUMP			640. ⁰⁰	1,280. ⁰⁰
2	SBK-1500	STABILIZER BAR KIT			75. ⁰⁰	150. ⁰⁰
2	10P-0152	DOUBLE POPPET, EMERGENCY SHEAR VALVE			230. ⁰⁰	460. ⁰⁰
1	DSL-PKG	HOSE, NOZZLE, SWIVEL, BREAK-AWAY, WHIP, DIESEL				395. ⁰⁰
1	UNL-PKG	HOSE, NOZZLE, SWIVEL, BREAK-AWAY, WHIP, UNLEADED				395. ⁰⁰
		UNDERGROUND TANK UPGRADE				
1	STP33-VL2	1/3HP FIXED SPEED SUBMERSIBLE PUMP				1,550. ⁰⁰
1	STP75-VL2	3/4HP FIXED SPEED SUBMERSIBLE PUMP				1,595. ⁰⁰
2	5800100215	STP-SCI SINGLE PHASE SMART CONTROLLER			255. ⁰⁰	510. ⁰⁰
1	403168901	MECHANICAL LINE LEAK DETECTOR-GAS				365. ⁰⁰
1	403170901	MECHANICAL LINE LEAK DETECTOR-DIESEL				365. ⁰⁰
2	794380-351	VERDER-ROOT NON DISCRIMINATING SUMP SENSOR			695. ⁰⁰	1,390. ⁰⁰
2	TBA-4090	TANK FITTING ADAPTER-4"			225. ⁰⁰	450. ⁰⁰
2	TSM-4536	TANK SUMP, MEDIUM BURY			785. ⁰⁰	1,570. ⁰⁰
2	39CD-PL10	COMPOSITE COVER MANHOLE, PLAIN COVER/H RECESS HANDLE			1,010. ⁰⁰	2,020. ⁰⁰

Signature

APEC QUOTATION WORK FORM



Quotation To CITY OF POWDER SPRINGS
3006 SPRING IND. DR.
POWDER SPRINGS, GA. 30127

Phone Number 770-943-8013 Cell

Contact LATISHA HAMMONDS Email lhammonds@cityofpowdersprings.org

Date

Terms TBD

Install #

Quote #

QTY	Item Number	Description	MSRP	Cost	Sell	Total
2	6918-0700 IV	FULL PORT BALL VALVE-1.5"			65.00	130.00
50	C15A-	DOUBLE-WALL PRIMARY PIPE, 1.5"			30.00	1,500.00
4	SBC-2150	SWIVEL BOLT-ON COUPLING-1.5"			195.00	780.00
50	AXP40-	4" DUAL LAYER ACCESS PIPE			7.00	350.00
4	DEB-0150	DOUBLE ENTRY BOOT-PIPING			70.00	280.00
12	DEB-0751	DOUBLE ENTRY BOOT-CONDUIT			65.00	780.00
2						
		INSTALLATION TO INCLUDE:				
		PUMP OUT WATER FROM TWO (2) EXISTING UST TANK SUMPS;				
		DISPOSE OF; REMOVE TWO (2) EXISTING WAYNE MECHANICAL DISPENSERS,				
		HAUL AWAY FOR DISPOSAL; REMOVE EXISTING TWO (2) SUBMERSIBLE PUMPS,				
		HAUL AWAY FOR DISPOSAL; SAW CUT CONCRETE BREAK OUT AND REMOVE				
		AROUND EXISTING UST SUBMERSIBLE PUMP MANHOLES; REMOVE				
		EXISTING CULVERT AND DEFECTIVE/ LEAKING TANK SUMPS; SAW CUT				
		CONCRETE BREAK-OUT AND REMOVE ON EXISTING ISLAND TO				
		ACCOMMODATE INSTALLATION OF NEW POLY DISPENSER SUMPS; SAW CUT				
		CONCRETE BREAK-OUT AND REMOVE, EXCAVATE DITCHES FROM ISLAND				
		TO TANK'S; INSTALL NEW TANK SUMPS & DISPENSER SUMPS; INSTALL				
		NEW SUBMERSIBLE PUMPS; INSTALL DOUBLE WALL PRIMARY PIPING				
		WITHIN 4" ACCESS PIPE; AIR TEST PIPING. INSTALL NEW SUMP SENSORS				

Installation To Include:

NO. 108 WATER FROM TWO EXISTING 1150 TANK SUMPS

DISPOSE OF: REMOVE TWO (2) EXISTING WAYNE MECHANICAL DISPENSERS,

HAUL AWAY FOR DISPOSAL: REMOVE EXISTING TWO (2) SUBMERSIBLE PUMPS,

HAUL AWAY FOR DISPOSAL: SAW CUT CONCRETE BREAK OUT AND REMOVE

AROUND EXISTING UST SUBMERSIBLE PUMP MANHOLES: REMOVE

EXISTING CULVERT AND DEFECTIVE/ LEAKING TANK SUMPS: SAW CUT

CONCRETE BREAK-OUT AND REMOVE ON EXISTING ISLAND TO

ACCOMMODATE INSTALLATION OF NEW POLY DISPENSER SUMP; SAW CUT



CONCRETE BREAK-OUT AND REMOVE EXCAVATE DITCHES FROM ISLAND

TO TANKS: INSTALL NEW TANK SUMPS & DISPENSER SUMPS. INSTALL

NEW SUITABLE PUMPS: INSTALL DOUBLE WALL PRIMARY PIPING

WITHIN 4" ACCESS PIPE: AIR TEST PIPING. INSTALL NEW SUMP SENSORS

Signature



APEC QUOTATION WORK FORM

Quotation To CITY OF POWDER SPRINGS Date _____
3006 SPRING IND. DR. Terms TBD
POWDER SPRINGS, GA. 30127 Install # _____
Phone Number 770-943-8013 Cell _____ Quote # _____

Contact LATISHA HAMMONDS Email lhammonds@cityofpowdersprings.org

QTY	Item Number	Description	MSRP	Cost	Sell	Total
		NOTE: ALL EXISTING ELECTRICAL (DISPENSER, SUBMERSIBLE PUMPS, FUEL MASTER, VEEDER-ROOT, ETC. POWER WIRING / LOW VOLT COM.) IS TO BE RE-USED. IF ANY EXISTING CONDUITS, WIRING, SEAL-OFFS, ETC ARE FOUND TO BE NON USABLE AND REQUIRE REPAIRS OR REPLACEMENT A CHANGE ORDER WILL BE REQUIRED. AND WORK WILL BE PERFORMED ON A "TIME AND MATERIAL BASIS". BACKFILL EXCAVATED AREAS WITH WASHED STONE. SET MANHOLES; INSTALL DOWEL PINS AND RE-POUR CONCRETE; DELIVER SET ANCHOR NEW DISPENSERS; MAKE FINAL ELECTRICAL AND PIPING CONNECTIONS; PURGE SYSTEM, CHECK CALIBRATION; TEST & TRAIN IN PROPER OPERATION; CLEAN OUR CONSTRUCTION DEBRIS FROM JOBSITE.				
		NOTE: IF OUR INSTALLATION INVOLVES TYING INTO EXISTING TANKS, PIPING, ELECTRICAL CONDUITS, WIRING, PANELS, OR OTHER ELECTRICAL EQUIPMENT, OR USING CUSTOMER PROVIDED NEW OR USED EQUIPMENT, APEC WARRANTS ONLY THAT SUCH ITEMS ARE NON-LEAKING AND SERVICEABLE ONLY AT THE TIME OF OUR INSTALLATION.				
		NOTE: NO LOADING, HAULING OR DISPOSAL OF CONTAMINATED SOIL INCLUDED IN QUOTE				
		EQUIPMENT AS ABOVE:				25,305.00
		INSTALLATION:				23,540.00
		TOTAL:				48,845.00
		ADD:				2,650.00
		ADDER: PERFORM GA. EPD LINE CLOSURE				51,495.00

Signature